



- . **Title:** Industrialised Construction: A New Chapter Beyond MMC
- . **Subtitle:** Understanding the Shift from Modularity to Process-Driven Assembly
- . **Presented by:** Strata | May 2025





- **What is Industrialised Construction?**

- Process-driven, not product-led
- Applies advanced manufacturing principles (standardisation, automation, DfMA)
- Focuses on repeatable components assembled onsite
- Aims for improved speed, quality, compliance, and cost-efficiency





- **Why Industrialised Construction Now?**

- Addressing legacy inefficiencies in construction
- Enabling decarbonisation and whole-life value
- Aligning with Government frameworks and mandates (e.g. Construction Playbook, BSA)
- Mitigating skills shortages via factory-based roles

Aspect	Industrialised Construction	Modular Construction
Form	Kit-of-parts / components	Whole-box volumetric modules
Flexibility	High – hybrid/panelised/volumetric	Low – fixed dimensions/layouts
Supply Chain	Open, non-proprietary	Closed, vertically integrated
Assembly	Onsite assembly	Modules delivered 80–90% complete
Logistics	Flat-pack, and pods, efficient	Bulky transport needs
Risk Profile	Low – diversified suppliers	High – single point of failure

Industrialised vs Modular Construction



- **MMC Didn't Fail – Execution Did**

- Over-promised, under-delivered
- Key reasons modular housing failed:
 - Unrealistic investor expectations
 - Closed, IP-heavy systems
 - Factory overheads + demand uncertainty
 - Supply chain resistance
 - Regulatory headwinds (post-Grenfell)
 - Cultural scepticism (planning/funding)



TOP TEN MMC ERRORS	THE PROBLEM	THE SOLUTION
Wrong Team & Collaboration	Not employing the right team members from day one and unable to think from first principles	Get the right team together! Find experienced and proactive consultants who share your values
Procurement Routes	A D&B procurement route is problematic unless contractors are brought onboard early	Use sub-contractors, work with manufacturers, using a PCSA from early in the design process
High capital expenditure & funding gaps	Spending too much money upfront increases the risk of catastrophic failure	Start small, test, feedback mistakes and then scale. Look for funding opportunities
Too much complexity	Choice is good, but can also be bad – too much choice creates manufacturing process inefficiencies and errors	Narrow down the choice to only what is essential to offer consumers and has the greatest impact
Over Designed and Engineered	Too much material through over engineering creates increased costs plus bad architecture!	Keep it simple. Don't over think it and overdesign. Consider aligning with NHBC etc
Lack of Pipeline & availability of Land	No ownership of land or insufficient pipeline of clients with land	Owning suitable land is king, safeguarding your own pipeline. Only produce what is required
Site conditions & transport	Site topography, other features and access can be problematic meaning viability is an issue	Consider designing elements to be small and nimble and design in for difficult sites
Built in Design Flexibility	Spending time and money creating a design which can't be adapted to future needs	Design in for flexibility without returning to the drawing board and consider iterations
Design and manufacturing interaction	Lack of communication between the design team and manufacturing team getting it built	Close collaboration is essential, keeping golden thread of communication clear and

HOME OF 2030



MOBIE
Ministry of Building
Innovation and Education

RIBA



HM Government

1. **Age Friendly and Inclusive Living** - address a gap in the housing market for new homes which appeal to and cater for a variety of age groups, adaptable to changing uses and needs over lifetime for a healthy and inclusive community.
2. **Low Environmental Impact** – applying technology and construction techniques that will deliver net zero emissions and high quality outcomes, reduced fuel bills and improved occupant health.
3. **Healthy Living** – promoting better health and wellbeing to enhance quality of life within homes.
4. **Deliverable and Scalable** – solutions that can deliver market needs at scale and are cost-effective.




HOME OF
2030

A Public Vision for the Home of 2030







The Positive+ House




Integrated digital process




Adopting a distributed manufacturing approach, enables component-driven flexibility through a fully integrated digital process working directly with suppliers and manufactures.



Getting the ingredients right




Understanding the building's constituent parts allows for future flexibility to accommodate user changing needs and allows for easier disassembly and component re-use at end of life.



Reducing waste

Our unified approach absorbs carbon emissions, promotes low toxicity and highlights the value of future resources. People are increasingly adapting their consumption habits to make their own personal contributions to addressing climate change. Our design approach anticipates and enables this transition. We aim to enhance the entire production process, using biogenic resources to redress environmental failures in our built environment.



Procuring Value

Embodied Carbon Storage Benefit of £21/m2

Savings to the NHS

£750/year saving on energy bills and £33/m2 saving on carbon over 60 years

Local employment opportunities in near site factories

Natural	Human	Social	Manufactured	Economic
<div>Preference for bio-based (natural) material for embodied carbon reductions and carbon storage.</div> <div>Design for manufacture, assembly and disassembly (DfMA+D) approach using standardised products, and end of first use approaches to enhance circular economy opportunities.</div> <div>UK specific species grades adopted to make demand side changes to promote home grown timber. CLT tested for UK specific C16+ and native Douglas Fir use. Partnering with local CLT producer start-up for supply.</div> <div>Improved resource use and transport impact reductions through standardisation, optimisation and rationalisation and reduction of transport and assembly impacts in other off-site methods.</div>	<div>Breathable facade and natural material provides increased respiratory and health benefits to users.</div> <div>Connection to landscaping at home and in the community level provides enhanced well being.</div> <div>Improved thermal comfort in future extreme weather events by improved fabric standards and use of external shading.</div> <div>High levels on internal natural daylighting by consideration of window location and sizes.</div>	<div>Local assembly employment opportunities and skills training at near-site flying factory</div> <div>Balance between open shared urban spaces and private gardens for peace and privacy.</div> <div>Community sharing centre and repair cafe, communal areas and 'edible landscaping' and allotments sites support a community circular economy, the use of products as service, local producers, seasonal food.</div> <div>Re/up-skilling opportunities within communities and regions around assembly methods rather than multiple site trades.</div> <div>Masterplan encourages walking and cycling for improved health and wellbeing.</div>	<div>Distributed manufacturing and 'Panel & Chunk' approach for easier adoption of advanced MMC methods and multiple supplier sourcing delivering PMV of c.76%.</div> <div>Mass timber and joisted floor approach allows easier adaption by users or builders using simple carpentry methods. Demountable walls allow reconfiguration of spaces. Services upgradeable and accessible for maintenance.</div> <div>Adoption of digital twin and supply chain own digitalisation as methods for coordination, delivery and retention of material data.</div> <div>User focused quality providing added comfort through passive fabric design, shading and simple controls.</div> <div>Option for basic shell delivery to allow fit out by users based on their own design, needs and budgets.</div>	<div>Reduced capital investment for MMC methods using supplier manufacturing approach.</div> <div>Reduced site rework and rectification of defects through 'field factory' quality control and simplification of detailing requirements to meet Passivhaus standards. Reduction in claims and costs.</div> <div>Low energy bills for occupants using Passivhaus standards.</div> <div>Incorporated climate resilience to avoid future upgrade costs.</div>

DASHBOARD

Premanufacturing Value (PMV) of 77%

Consumes 1830 kWh per year for heating,
about 15% of the average UK household

(A1-A3) is 198 kgCO₂/m²,
and biogenic storage of 340 kg/cO₂/m²

Net A1-A3 + biogenic
-142 kgCO₂/m²

Passivhaus Plus

PER demand 55kWh/(m²TFA.a)

PER generation 68kWh/(m²Projected.a)

£2,075/m² net construction cost

The Positive⁺ House

Waste type (see examples below)	Total mass in house (kg)	Assumed waste rate % (by mass) *	Expected waste amount (tonnes) per average 100m ² house
Compacted (clean) hardcore	19,665.00	10.00%	1.425
Concrete in ground floor	49,680.00	6.00%	2.16
CLT	16,187.50	5.00%	0.59
Woodfibre insulation	7,931.00	5.00%	0.29
Treated timber facade	1,595.54	10.00%	0.12
Triple glazing	1,398.30	5.00%	0.05
Plasterboard	3,096.00	15.00%	0.34
Cabling	not measured	10.00%	
CLT plastic packaging	not measured	100.00%	
Timber battens (facades/floors)	2,571.26	15.00%	0.28

- **Why Industrialised Construction is Different, or is it just rebranding of the tired term MMC**

- Open, interoperable component systems
- Factory capacity already exists in UK (hundreds of suppliers)
- Lower risk, non-binary adoption: no “live or die” dependency
- Enables step-by-step integration into Tier 1 workflows







- **Global Drivers for Industrialised Construction**

- Housing shortages
- Need for faster, safer, cleaner delivery
- Ageing and shrinking construction workforce
- Carbon and waste reduction imperatives
- Digitisation (BIM, digital twins, Industry 4.0)
- Policy drivers: Playbook, UN SDGs, Green Deal

- **Is Industrialised Construction Still MMC?** Yes, but broader in scope:
 - **MMC Category 2:** Panelised structural systems
 - **MMC Category 5:** Sub-assemblies (pods, stairs, facades)
 - **MMC Category 7:** Site process improvements
- **BUT:**
 - Industrialised Construction avoids MMC's stigma
 - Focuses on outcomes: compliance, cost, carbon, delivery




Project / Client View




Direction of travel, Traditional, closed offsite, open offsite and Industrialised

TRADITIONAL CONSTRUCTION




OFFSITE PROCUREMENT




Industrialized Construction

Main contractor delivers electric trichucy offsite



Closed Offsite risks versa Traditional.



OFFSITE (CLOSED)

Int / Ext walls

DFMA design and engineer

PCC Planks & Stairs

Floor cassettes

Erector

Roof

Crane

Main Contractor

**Above
the line**

**Below
the line**

Crane

Site Team

Sub-contractors

PCC Planks & Stairs

Design and Engineering

SFS / drylining / Frame / walls

TRADITIONAL CONSTRUCTION

OUT-SOURCING, ONCE AND SOMETIMES TWICE

Designer

Engineer

PC design

PC Factory

Floor designer

Floor factory

Installer

Roof designer

Roof Factory

Plant

Industrialised Construction.

**MAIN
CONTRACTOR**

Int / Ext walls

DFMA design and engineer

PCC Planks & Stairs

Floor cassettes

Erector


Roof

Crane

Industrialised Construction / Traditional procurement



**MAIN
CONTRACTOR**



Wall designer Wall Factory

Designer

Engineer

PC design PC Factory

Floor designer Floor factory

Installer

Roof designer Roof Factory

Plant

A Modular House

For an SME developer in the East Midlands

- Micro-volumetric Modular
- Kit-of-parts design approach
- Affordable @ £1,300/m²
- Passivhaus Classic homes
- Octopus Zero-bills Tariff
- Biogenic materials used
- Ability for owners to adapt
- Designed for disassembly
- Designed to minimize waste



A Modular House

For an SME developer in the East Midlands



- Micro-volumetric Modular
- Kit-of-parts design approach
- Affordable @ £1,300/m²
- Passivhaus Classic homes
- Octopus Zero-bills Tariff
- Biogenic materials used
- Ability for owners to adapt
- Designed for disassembly
- Designed to minimize waste

perpendicular
ENGENUITY
Integration



planningprospects
planning and development consultancy



CHPK / ACT
building control & fire engineering



What is open source OSKOP?

A **non-proprietary, standardised** approach to component-led offsite construction.

Enables **interoperability across multiple UK factories** (e.g. NZP, OEP, Timber Innovations).

Developed to support compliance with **DfE Output Specifications, Building Safety Act 2022, and Construction Playbook** principles.

Freely shared format to **de-risk procurement**, especially for **Tier 1/2/3 contractors and public sector clients**.



Key Features

- **Component-led**, not system-led: internal walls, external walls, floors, roofs, stairs, and services coordinated as interchangeable sub-assemblies.
- Supports **hybrid panel systems** (e.g. concrete floors, steel composites, Timber and so on), while specific.
- Developed around **tested wall build-ups** for public buildings, including affordable housing, robust acoustic and thermal compliance.
- Compatible with **multiple insulation formats**, 60-year design life, structural element protection and tested wall build ups.

Supply Chain & Procurement Advantages

Open access means components can be competitively sourced from multiple regional factories.

Reduces over-reliance on vertically integrated or proprietary systems (e.g. modular boxes).

Compatible with **DfMA workflows** and digital tools (Revit, IFC, COBie formats).

Enables **direct contractor-led procurement** of compliant components (e.g. roof panels from A, walls from B, floor cassettes from C).

De-risks mini-competition and direct award on frameworks like **CF25**, **Crown Commercial Services**, and **NHS SBS**.



Version 3.5 - April 2025

The OSKOP 'Kit-of-Parts' Manufacturers Guide

**UNLOCKING
PUBLIC SECTOR
CONSTRUCTION**

Adaptable and Future-Ready

Designed for **incremental adoption**—can start with a single element (e.g. standardised wall) and scale.

Integrates with **Foundation systems**, **SIPs alternatives**, and **low-carbon retrofit** strategies.


Promotes a **circular economy** model through repeatable design, disassembly potential, and material transparency.

Enables localisation—Welsh timber, Kent offsite firms, Northern innovation hubs.



FINAL THOUGHT

“INDUSTRIALISED CONSTRUCTION ISN’T A METHOD—IT’S A MINDSET. ONE THAT SEES THE FUTURE OF BUILDING NOT AS DISRUPTION, BUT EVOLUTION.”



STRATA DOESN’T DEFINE ITS BUSINESS BY METHODS—BUT BY OUTCOMES. WE’VE WALKED THE PATH FROM MODULAR HYPE TO INDUSTRIALISED MATURITY. LET US HELP YOU NAVIGATE WHAT’S NEXT.



STRATA


Solutions For Real Estate

Solutions for the Real Estate and Construction Industry

Contact Us

- **Why Choose Strata**
 - Board has 35+ years of MMC and Industrialisation expertise
 - Balanced view: traditional vs modern methods
 - Not wedded to a single system or solution
- Supports clients through:
 - Supply chain integration
 - Risk and compliance management
 - DfMA and digital workflows
 - ESG and cost analysis

www.perpendicular.co.uk
hello@perpendicular.co.uk



Creating homes for
our future, together
perpendicular

