


CIVIC

Tall Buildings Conference – iQ Chandos House

March 2026

**thriving
together**



About Us


Civic is a team of system thinkers in the built environment.

We're creating positive impact for people, place and the planet.

Given the climate and societal change we must respond to and recognising that the environment functions as a single system, we've carefully curated a team centred around built environment engineering, alongside transport, heritage, archaeology, sustainability, and place-based consultancy.

Team Civic is united by its creative belief, bringing art and science together to solve problems. Together we're thoughtful, considerate disruptors with a clear mission - to care for and protect our climate and communities.

We are passionate about our responsibility to leave a positive legacy through our work, for neighbourhoods now and the next generation. This is reflected in the vision we have set ourselves of having a positive impact on the environment and enabling people to lead healthier and happier lives.



CIVIC

Our Locations




Our Space



CIVIC


Emotional Intelligence



Our Conscience



- We have always pursued a sustainable design agenda, prioritised nature-based solutions & made well-informed decisions guided by our vision and values
- Initially, we set this out as our 'Climate Charter'
- Over time, we realised this wasn't an accurate reflection of our responsibilities and our impact
- This inspired us to develop 'our conscience'
- It's our response to the ESG agenda & is a 'living' framework designed to reflect the people we are, how we behave, feel, collaborate and act



CIVIC

iQ Chandos House

Manchester




iQ Chandos House, Manchester

Client: iQ Student Accommodation

Architect: Sheppard Robson

Contractor: Bowmer and Kirkland

Existing Site (Civic) Day 0






CIVIC




iQ Chandos House, Manchester

CIVIC




CIVIC

In The Ground - Piles



In The Ground - Piles




Type	Total No.	Length (L)	Width (W)	Depth (D)	Edge (E)	Embedment (E)
PC-2	26	1050	3300	1800	525	75
PC-3	9	3000	3300	1800	525	75
PC-4	1	3300	3300	1800	525	75
PC-10	1	10050	3300	1800	525	75
PC-10a	1	10550	3250	1800	525	75
PC-11	1	4285	6675	1800	525	75
PC-14	1	5550	8550	1800	525	75
PC-CORE A	1	12250	14550	2500	525	75
PC-CORE B	1	10440	12300	2500	525	75
PC-CORE C	1	12395	12300	2500	525	75
PC-TC1	1	6860	7180	2100	Varies	175
PC-TC2	1	8200	8330	2000	Varies	75

Type	Depth (mm)	Width (mm)
GB-1	600	600

Residual Risk
Basement and Foundations
Overloading of Vimto Park retaining wall: Historic record calculations for the Vimto Park wall indicate that the original design did not allow for surcharge loading. Excavation zone width equal to the retained height of the existing wall to be adopted until the completion of the backfill between the existing and new wall is complete.
Unexploded Ordnance: Site is classified as medium risk of encountering unexploded ordnance. Refer to detailed UXO risk assessment for recommendations.
Existing foundations: It has not currently been possible to obtain through ground investigation the depth, extent and nature of the existing Chandos House foundations. Record drawings have been obtained which identify piled foundations on an irregular grid are present. The Mott MacDonald foundation design has taken cognisance in the existing foundation arrangement and have set an exclusion zone around existing foundations to allow for out of plan position and out of vertically tolerance of the foundations to reduce the risk of encountering existing foundations in the piling works.
Tower crane in close proximity to Network Rail assets: Collapse of tower cranes and/or falling materials from the crane onto the railway viaduct or other adjacent areas. Method statement to consider filling adjacent to third party properties. Tower crane foundation will need to be CAT3 checked by an appropriately qualified engineer for Network Rail Approval.
Building in close proximity to Network Rail structures: Risk that ground movements occur which are detrimental to Network Rail properties. Monitoring to be carried out and action levels agreed in accordance with Network Rail requirements.
Collapsing of contiguous walls: Deep foundations are required, risk of undermining the boundary retaining walls. Construction sequence and maximum depth of excavation to be agreed with the Contractor and designed for by the piling subcontractor.

- Notes
- This drawing is to be read in conjunction with the General Notes drawing: ECHO-MMD-ZZ-XX-DR-S-0001 & Mott MacDonald Design Risk Schedule: ECHO-MMD-ZZ-XX-SH-S-0001.
 - Do not scale from this drawing.
 - All dimensions and in millimetres U.N.O.
 - All levels are in metres U.N.O.
 - All Columns are aligned to the slab edge unless noted otherwise.
 - For reinforcement rates and steelwork allowances refer to report ref: ECHO-MMD-XX-XX-RP-S-0003.



Reference drawings

Rev	Date	Drawn	Description	CHK'd	App'd
C03	07.05.2020	MES	PC-TC1 Revised	AJS	IMB
C02	17.04.2020	MES	Revised as Clouded, PC-TC1 Abeyance Cloud Removed	AJS	IMB
C01	13.02.2020	AUL	Construction Issue	AJS	IMB

Status Stamp

CONSTRUCTION

MOTT MACDONALD

Mott MacDonald
4th Floor
Derwent House
150 Arundel Gate
Sheffield
S1 2JY
United Kingdom


Client: **iQ Student Accommodation**

VINCI CONSTRUCTION | **UK**

Title: **Echo Street Foundations General Arrangement Sheet 2**

Designed	W.Jebb	WJ	Eng. check.	A.Simpson	AS
Drawn	A.Longden	AUL	Coordination	J.Sivola	JS
Dwg check.	A.Simpson	AS	Approved	L.Berford	IMB
MMD Project Number	402052	Scale at A1	1:100	Security	STD
Suitability Description	Suitable For Construction	Scale at A1	1:100	Suit. Code	A5
Drawing Number	ECHO-MMD-ZZ-FN-DR-S-00211	Scale at A1	1:100	Rev	C03

In The Ground - Piles



Residual Risk

Basement and Foundations

Overloading of Vinto Park retaining wall: Historic record calculations for the Vinto Park wall indicate that the original design did not allow for surcharge loading. Exclusion zone width equal to the retained height of the existing wall to be adopted until the completion of the backfill between the existing and new wall is complete.

Temporary stability of Granby Row retaining wall: Risk of collapse when toe is demolished. Temporary propping of the Granby Row retaining wall to be provided until new wall is constructed and fully backfilled.

Unexploded Ordnance: Site is classified as medium risk of encountering unexploded ordnance. Refer to detailed UXO risk assessment for recommendations.

Existing foundations: It has not currently been possible to obtain through ground investigation the depth, extent and nature of the existing Chandos House foundations. Record drawings have been obtained which identify piled foundations on an irregular grid are present. The Mott MacDonald foundation design has taken cognisance in the existing foundation arrangement and have set an exclusion zone around existing foundations to allow for out of plan position and out of verticality tolerance of the foundations to reduce the risk of encountering existing foundations in the pile works.

Tower crane in close proximity to Network Rail assets: Collapse of tower cranes and/or falling materials from the crane onto the railway viaduct or other adjacent areas. Method statement to consider lifting adjacent to third party properties. Tower crane foundation will need to be CA13 checked by an appropriately qualified engineer for Network Rail Approval.

Building in close proximity to Network Rail structures: Risk that ground movements occur which are detrimental to Network Rail properties. Monitoring to be carried out and action levels agreed in accordance with Network Rail requirements.


Collapse of contiguous walls: Deep foundations are required, risk of undermining the boundary retaining walls. Construction sequence and maximum depth of excavation to be agreed with the Contractor and designed for by the piling subcontractor.

Block A - Pile Schedule

Pile Ref	Pile Dia Ø (mm)	Pile Cut-Off Level (mAOD)	Minimum Embedment (mm)	Easting (m)	Northing (m)	Vertical Actions						Horizontal Actions	
						Ed SLS Comb (Max) (kN)	Ed SLS Comb (Min) (kN)	Ed Set B (A1) ULS Comb (Max) (kN)	Ed Set B (A1) ULS Comb (Min) (kN)	Ed Set C (A2) ULS Comb (Max) (kN)	Ed Set C (A2) ULS Comb (Min) (kN)	Ed Set B (A1) ULS Comb (kN)	Ed Set C (A2) ULS Comb (kN)
CPA001	750	34.170	75	384640.889	397707.206	2500	100	3500	100	2700	100	100	90
CPA002	750	34.170	75	384643.009	397707.960	2500	100	3500	100	2700	100	100	90
CPA003	750	34.170	75	384645.129	397708.715	2500	100	3500	100	2700	100	100	90
CPA004	750	34.170	75	384647.248	397709.469	2500	100	3500	100	2700	100	100	90
CPA005	750	34.170	75	384649.368	397710.224	2500	100	3500	100	2700	100	100	90
CPA006	750	34.170	75	384651.488	397710.978	2500	100	3500	100	2700	100	100	90
CPA007	750	34.170	75	384653.608	397711.732	2500	100	3500	100	2700	100	100	90
CPA008	750	34.170	75	384641.694	397704.945	2500	100	3500	100	2700	100	100	90
CPA009	750	34.170	75	384643.814	397705.699	2500	100	3500	100	2700	100	100	90
CPA010	750	34.170	75	384645.933	397706.454	2500	100	3500	100	2700	100	100	90
CPA011	750	34.170	75	384648.053	397707.208	2500	100	3500	100	2700	100	100	90
CPA012	750	34.170	75	384650.173	397707.962	2500	100	3500	100	2700	100	100	90
CPA013	750	34.170	75	384652.293	397708.717	2500	100	3500	100	2700	100	100	90
CPA014	750	34.170	75	384654.412	397709.471	2500	100	3500	100	2700	100	100	90
CPA015	750	34.170	75	384642.700	397702.119	2500	100	3500	100	2700	100	100	90
CPA016	750	34.170	75	384644.819	397702.873	2500	100	3500	100	2700	100	100	90
CPA017	750	34.170	75	384646.939	397703.627	2500	100	3500	100	2700	100	100	90
CPA018	750	34.170	75	384649.059	397704.382	2500	100	3500	100	2700	100	100	90
CPA019	750	34.170	75	384651.179	397705.136	2500	100	3500	100	2700	100	100	90
CPA020	750	34.170	75	384653.298	397705.890	2500	100	3500	100	2700	100	100	90
CPA021	750	34.170	75	384655.418	397706.645	2500	100	3500	100	2700	100	100	90
CPA022	750	34.170	75	384643.672	397699.386	2500	100	3500	100	2700	100	100	90
CPA023	750	34.170	75	384645.792	397700.141	2500	100	3500	100	2700	100	100	90
CPA024	750	34.170	75	384647.911	397700.895	2500	100	3500	100	2700	100	100	90
CPA025	750	34.170	75	384650.031	397701.650	2500	100	3500	100	2700	100	100	90
CPA026	750	34.170	75	384652.151	397702.404	2500	100	3500	100	2700	100	100	90
CPA027	750	34.170	75	384654.271	397703.158	2500	100	3500	100	2700	100	100	90
CPA028	750	34.170	75	384656.391	397703.913	2500	100	3500	100	2700	100	100	90
CPA029	750	34.170	75	384644.644	397696.654	2500	100	3500	100	2700	100	100	90
CPA030	750	34.170	75	384646.764	397697.409	2500	100	3500	100	2700	100	100	90
CPA031	750	34.170	75	384648.884	397698.163	2500	100	3500	100	2700	100	100	90
CPA032	750	34.170	75	384651.004	397698.917	2500	100	3500	100	2700	100	100	90
CPA033	750	34.170	75	384653.123	397699.672	2500	100	3500	100	2700	100	100	90
CPA034	750	34.170	75	384655.243	397700.426	2500	100	3500	100	2700	100	100	90
CPA035	750	34.170	75	384657.363	397701.181	2500	100	3500	100	2700	100	100	90
CPA036	750	34.870	75	384647.416	397696.297	3500	2300	5000	2300	3800	2300	0	0
CPA037	750	34.870	75	384647.010	397694.083	1300	800	1900	800	1400	800	0	0
CPA038	750	34.870	75	384649.130	397694.837	1300	800	1900	800	1400	800	0	0
CPA039	750	34.870	75	384653.232	397696.828	1900	1100	2700	1100	2100	1100	0	0
CPA040	750	34.870	75	384655.351	397697.582	1900	1100	2700	1100	2100	1100	0	0
CPA041	750	34.870	75	384648.978	397688.933	2400	200	3300	100	2500	200	40	40
CPA042	750	34.870	75	384651.097	397689.687	2400	200	3300	100	2500	200	40	40
CPA043	750	34.870	75	384653.217	397690.441	2400	200	3300	100	2500	200	40	40
CPA044	750	34.870	75	384655.337	397691.195	2400	200	3300	100	2500	200	40	40
CPA045	750	34.870	75	384657.457	397691.949	2400	200	3300	100	2500	200	40	40
CPA046	750	34.870	75	384649.648	397687.048	2400	200	3300	100	2500	200	40	40
CPA047	750	34.870	75	384651.768	397687.803	2400	200	3300	100	2500	200	40	40
CPA048	750	34.870	75	384654.123	397688.641	2400	200	3300	100	2500	200	40	40
CPA049	750	34.870	75	384656.545	397689.479	2400	200	3300	100	2500	200	40	40
CPA050	750	34.870	75	384658.967	397690.317	2400	200	3300	100	2500	200	40	40
CPA051	750	34.870	75	384651.808	397683.955	2300	1400	3200	1400	2500	1400	0	0
CPA052	750	34.870	75	384651.402	397681.740	2300	1400	3200	1400	2500	1400	0	0
CPA053	750	34.870	75	384653.522	397682.584	2300	1400	3200	1400	2500	1400	0	0
CPA054	750	34.870	75	384658.151	397686.212	1400	900	2000	900	1600	900	0	0
CPA055	750	34.870	75	384657.745	397683.998	1400	900	2000	900	1600	900	0	0
CPA056	750	34.870	75	384659.864	397684.752	1400	900	2000	900	1600	900	0	0
CPA057	750	34.870	75	384661.415	397687.520	400	200	700	200	500	200	0	0
CPA058	750	34.870	75	384662.170	397685.400	500	300	900	300	700	300	0	0
CPA059	750	34.870	75	384659.312	397713.085	1900	1200	2700	1200	2100	1200	0	0
CPA060	750	34.870	75	384660.066	397710.965	1900	1200	2700	1200	2100	1200	0	0
CPA061	750	34.870	75	384661.235	397707.682	1200	700	1700	700	1300	700	0	0
CPA062	750	34.870	75	384661.989	397705.562	1200	700	1700	700	1300	700	0	0
CPA063	750	34.870	75	384667.784	397689.786	400	200	600	200	500	200	0	0
CPA064	750	34.870	75	384668.538	397687.666	500	300	800	300	600	300	0	0
CPA080	900	34.670	75	384658.302	397698.737	4150	-550	5500	-1050	4750	-800	90	75
CPA081	900	34.670	75	384664.379	397700.899	4150	-550	5500	-1050	4750	-800	90	75
CPA082	900	34.670	75	384660.465	397692.660	4150	-550	5500	-1050	4750	-800	90	75
CPA083	900	34.670	75	384666.541	397694.823	4150	-550	5500	-1050	4750	-800	90	75

Notes

- This drawing is to be read in conjunction with the General Notes drawing: ECHO-MMD-ZZ-XX-DR-S-0001 & Mott MacDonald Design Risk Schedule: ECHO-MMD-ZZ-XX-SH-S-0001.
- Do not scale from this drawing.
- All dimensions are in metres U.N.O.
- All levels are in metres U.N.O.
- For reinforcement rates and steelwork allowances refer to report ref: ECHO-MMD-XX-XX-RP-S-0003.



Reference drawings

Block A Pile Schedule	ECHO-MMD-ZZ-PL-DR-S-00202
Block B Pile Schedule	ECHO-MMD-ZZ-PL-DR-S-00203
Block C Pile Schedule	ECHO-MMD-ZZ-PL-DR-S-00204
Granby Row Coreig Wall Pile Schedule	ECHO-MMD-ZZ-PL-DR-S-00205
Vinto Park Coreig Wall Pile Schedule	ECHO-MMD-ZZ-PL-DR-S-00206
Griline 12 Coreig Wall Pile Schedule	ECHO-MMD-ZZ-PL-DR-S-00206

CONSTRUCTION

Mott MacDonald
4th Floor
Derwent House
150 Arundel Gate
Sheffield
S1 2JY
United Kingdom

Client: IQ Student Accommodation

VINCI CONSTRUCTION UK

Echo Street Pile General Arrangement Sheet 1


Designed	W. Jeeb	WJ	Eng. check.	A. Simpson	AS
Drawn	A. Longton	AL	Coordination	J. Sivilis	JS
Dwg. check.	A. Simpson	AS	Approved	I. Barfoot	IB
MMD Project Number	Scale at A1	Security			
402052	1:100	STD			
Suitability Description		Suit. Code			
Suitable For Construction		A5			
Drawing Number		Rev			
ECHO-MMD-ZZ-PL-DR-S-00200		C02			

Block A - Temporary Pile Schedule

Pile Ref	Pile Dia Ø (mm)	Pile Cut-Off Level (mAOD)	Minimum Embedment (mm)	Easting (m)	Northing (m)	Vertical Actions						Horizontal Actions	
						Ed SLS Comb (Max) (kN)	Ed SLS Comb (Min) (kN)	Ed Set B (A1) ULS Comb (Max) (kN)	Ed Set B (A1) ULS Comb (Min) (kN)	Ed Set C (A2) ULS Comb (Max) (kN)	Ed Set C (A2) ULS Comb (Min) (kN)	Ed Set B (A1) ULS Comb (kN)	Ed Set C (A2) ULS Comb (kN)
TP001	750	38.390	0	384646.291	397679.231								
TP002	750	38.390	0	384647.139	397679.533								
TP003	750	38.390	0	384647.987	397679.835								
TP004	750	38.390	0	384648.834	397680.137								
TP005	750	38.390	0	384649.682	397680.438								
TP00													

In The Ground - Piles

ECHO-BSL-ZZ-PL-SH-X-00001 rev C02




Echo Street - Bearing Piles - NO TESTING
Manchester

Codes:	BS EN 1997-1:2004 & BS EN 1992-1-1:2004
Drawings:	ECHO-MMD-ZZ-PL-DR-5-00202 rev C02 ECHO-MMD-ZZ-PL-DR-5-00203 rev C01 ECHO-MMD-ZZ-PL-DR-5-00204 rev C02

Sheet:	of
Enq. No:	127850
Contr. No:	
Calc. by:	LJE
Revision:	C02
Date:	25/03/2020

File Reference	Location	No of Piles	COMBINATION 1			COMBINATION 2			REPRESENTATIVE ACTIONS			PPL (mOD)	COL (mOD)	Pile Dia (mm)	Pile Depth (m)	Rock Socket (m)	Main R/F No	Main R/F Dia	Links Dia	Links Pitch	Required Anchorage (m)	Rebar Length (m)	Central Bar Type No	Central Bar Length (m)	Revision	Comments
			Vertical Action Max	Vertical Action Min	Horizontal Action	Vertical Action Max	Vertical Action Min	Horizontal Action	Vertical Action Max	Vertical Action Min	Horizontal Action															
CPA001	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA002	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA003	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA004	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA005	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA006	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA007	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA008	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA009	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA010	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA011	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA012	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA013	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA014	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA015	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA016	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA017	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA018	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA019	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA020	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA021	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA022	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA023	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA024	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA025	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA026	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA027	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA028	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA029	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA030	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA031	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA032	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA033	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA034	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA035	West	1	3500	100	100	2700	100	90	2500	100		38.700	34.170	750	11.20	3.50	8	B20	B10	@	275	0.685	9.0			
CPA036	West	1	5000	2300	0	3800	2300	0	3500	2300		38.700	34.870	750	13.20	5.50	8	B20	B8	@	300	0.685	7.0			
CPA037	West	1	1900	800	0	1400	800	0	1300	800		38.700	34.870	750	13.20	5.50	8	B20	B8	@	300	0.685	7.0			
CPA038	West	1	1900	800	0	1400	800	0	1300	800		38.700	34.870	750	13.20	5.50	8	B20	B8	@	300	0.685	7.0			
CPA039	West	1	2700	1100	0	2100	1100	0	1900	1100		38.700	34.870	600	11.20	3.50	6	B20	B8	@	275	0.685	7.0			
CPA040	West	1	2700	1100	0	2100	1100	0	1900	1100		38.700	34.870	600	11.20	3.50	6	B20	B8	@	275	0.685	7.0			
CPA041	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA042	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA043	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA044	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA045	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA046	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA047	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA048	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA049	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA050	West	1	3300	100	40	2500	200	40	2400	200		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA051	West	1	3200	1400	0	2500	1400	0	2300	1400		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA052	West	1	3200	1400	0	2500	1400	0	2300	1400		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA053	West	1	3200	1400	0	2500	1400	0	2300	1400		38.700	34.870	600	12.70	5.00	6	B20	B8	@	275	0.685	7.0			
CPA054	West	1	2000	900	0	1600	900	0	1400	900		38.700	34.870	600	10.70	3.00	6	B20	B8	@	275	0.685	7.0			
CPA055	West	1	2000	900	0	1600	900	0	1400	900		38.700	34.870	600	10.70	3.00	6	B20	B8	@	275	0.685	7.0			
CPA056	West	1	2000	900	0	1600	900	0	1400	900		38.700	34.870	600	10.70	3.00	6	B20	B8	@	275	0.685				

In The Ground - Piles





BACHY SOLETANCHE

ECHO STREET (Contract: N1425)

TCT (Continuous flight auger)

Date : 16/04/2020 Length : 11.80 m
 Drilling : 12:47:58 - 12:53:43 Concrete volume : 6.279 m³
 Concreting : 12:53:43 - 13:02:26 Pile concrete volume : 6.027 m³
 Pile diameter : 750 mm Overconsumption : 16 %

1/100 CPB100 DXTCT 1.67/dialogmx1783 5.15.21



Echo Street, Manchester – Bearing Pile Design

Contract / Enquiry Name	Echo Street, Manchester
Contract / Enquiry No.	N1425 / 127850
Document Reference Number	ECHO-BSL-ZZ-PL-RP-X-0001

Chris WALLBANK Date: 26/02/2020.....
 (Contract Manager)






Issue Status			
Revision	Status	Purpose	Date
P01	S3	1 st issue (Bearing pile design)	30/01/2020
P02	S3	Revision for changes and following MM comments	20/02/2020
C01	A5	For Construction (no changes from rev P02)	26/02/2020

Review within each individual Entity:


Author	Reviewed by	Approved by
Date: 26/02/20 Name: Lisa J Ellis Signature: <i>[Signature]</i>	Date: 26/02/20 Name: Ana T Carvalho Signature: <i>[Signature]</i>	Date: 26/02/20 Name: David A Hard Signature: <i>[Signature]</i>



In The Ground - Foundations



Investigations



Pile Load Test Report

SOC-FNDS-MLT-23-468.1

Contract Information

SOCOTEC UK Reference FNDS-23-468 **Contract Reference** C15436
Client Volker Ground Engineering **Client Contact** Bilal Kothia
Client Address Preston City Park
 Bluebell Way
 Preston
 PR2 5PE

Site Address Echo Street
 Manchester M1 3AL



Digitally signed
 by: Michael
 Plummer
 Date: 2023.08.29
 16:37:21 Z

Abstract

This report describes the load testing carried out by SOCOTEC UK at Echo Street - Manchester on CPB148. The data presented in this report represents a summary of the measured readings due to the volume obtained. Full data records can be provided upon request.


Summary

Increment	Load (kN)	Maximum Disp. (mm)	Residual Disp. (mm)
100% DVL	3500	2.77	
100% DVL + 50% SWL	5250	5.26	1.31

Revision History

Revision	Report Date	Issue Date	Author	Verifier	Revision Details
1	29/08/2023	29/08/2023	JH	MP	Initial Document

Figure 3 – Load vs. Displacement



Title						
The Bachy Solentanche Pile Design Report, Appendix C, records a design settlement criteria of 10mm at SLS representative load and 20mm at 1.5 x SLS representative load for a single pile.						
The below table presents the results from Socotec status load tests and compares these against the design settlement criteria of Bachy Solentanche design.						
Pile	Increment	Legacy Development Pile Schedule Load (SLS) (kN)	Load (kN)	Maximum Recorded Settlement (mm)	Design Settlement Criteria (mm)	Pass/Fail
CPA007	1.0 x SLS	2500	2500	1.56	10.0	Pass
	1.5 x SLS	N/A	3750	2.58	20.0	Pass
CPB142	1.0 x SLS	2400	2400	1.91	10.0	Pass
	1.5 x SLS	N/A	3600	3.07	20.0	Pass
CPB148	1.0 x SLS	3500	3500	2.77	10.0	Pass
	1.5 x SLS	N/A	5250	5.26	20.0	Pass
CPC283	1.0 x SLS	3200	3200	3.20	10.0	Pass
	1.5 x SLS	N/A	4800	6.86	20.0	Pass

Review of the pile loading test results show all piles operate within the allowable displacement limits.



Table/Sheet
1/1

Date of Test
18/8/23

CONCRETE TEST RESULTS
COMPRESSIVE STRENGTH AND DENSITY OF CORES
BS EN 12504-1:2019, BS EN 12390-3:2019 and BS EN 12390-7:2019

Sandberg Reference	F27129	F27130
Site Mark/Client Reference	C1	C2
Details: - Location Echo Street, Granby Row	GL 1H	GL 1D
- Date of coring	ND	ND
- Date received	4/8/23	4/8/23
Presence of abnormalities	None	None
Reinforcement, as received (diameter/distance) ¹ mm	None	None
Reinforcement, prepared (diameter/distance) ¹ mm	None	None
Aggregate, maximum nominal size mm	18	22
Condition on receipt	Wrapped	Wrapped
Storage conditions	Ambient air	Ambient air
Method of End preparation (Cap/Ground)	Ground	Ground
Actual Core Lengths		
- Core length, as received mm	302-314	298-304
- Relation to length, as-received mm	180-285	130-235
Mean Prepared Length mm	103	104
Mean Core Diameter d _m mm	99	99
Length/Diameter ratio of prepared specimen λ	1.04	1.05
Density ² - As received kg/m ³	2360	2380
Exposure time before Test 16-24h	✓	✓
Estimation of prepared core excess voidage %	1.5	2.0
Maximum Load at Failure kN	535	514
Compressive Strength ³ MPa (N/mm ²) (Measured Core Strength)	69.5	66.8
Mode of Failure ⁴	Normal	Normal
Deviations from standard	See footnote 2	See footnote 2
Remarks:		

1 Centre of bar to core end, before and after end preparation (eg. 20/100/40 = 20mm diameter bar, 100mm from the core end as-received and 40mm from the core end as-prepared.)
 2 Volume by measurement/water displacement, densities given to nearest 10kg/m³. Balance used complies to BSEN 12504-1:2009. (This will not reduce confidence in the test result.)
 3 Compressive strength values given to nearest 0.1 MPa (N/mm²).
 4 'Normal' (symmetrical failure) or otherwise as described.
 ND = Not determined. NA = Not applicable.




Table/Sheet
1/2

Date of Test
18/8/23


CONCRETE TEST RESULTS
COMPRESSIVE STRENGTH AND DENSITY OF CORES
BS EN 12504-1:2019, BS EN 12390-3:2019 and BS EN 12390-7:2019

Sandberg Reference	F27131	F27132
Site Mark/Client Reference	C3	C4
Details: - Location Echo Street, Granby Row	GL 4C	GL 10C
- Date of coring	ND	ND
- Date received	4/8/23	4/8/23
Presence of abnormalities	None	None
Reinforcement, as received (diameter/distance) ¹ mm	None	20/56, 25/82, 25/84
Reinforcement, prepared (diameter/distance) ¹ mm	None	None
Aggregate, maximum nominal size mm	18	24
Condition on receipt	Wrapped	Wrapped
Storage conditions	Ambient air	Ambient air
Method of End preparation (Cap/Ground)	Ground	Ground
Actual Core Lengths		
- Core length, as received mm	307-310	208-214
- Relation to length, as-received mm	170-275	100-200
Mean Prepared Length mm	104	99
Mean Core Diameter d _m mm	99	99
Length/Diameter ratio of prepared specimen λ	1.05	1.00
Density ² - As received kg/m ³	2360	2390
Exposure time before Test 16-24h	✓	✓
Estimation of prepared core excess voidage %	3.5	2.5
Maximum Load at Failure kN	569	550
Compressive Strength ³ MPa (N/mm ²) (Measured Core Strength)	73.9	71.4
Mode of Failure ⁴	Normal	Normal
Deviations from standard	See footnote 2	See footnote 2
Remarks:		


1 Centre of bar to core end, before and after end preparation (eg. 20/100/40 = 20mm diameter bar, 100mm from the core end as-received and 40mm from the core end as-prepared.)
 2 Volume by measurement/water displacement, densities given to nearest 10kg/m³. Balance used complies to BSEN 12504-1:2009. (This will not reduce confidence in the test result.)
 3 Compressive strength values given to nearest 0.1 MPa (N/mm²).
 4 'Normal' (symmetrical failure) or otherwise as described.
 ND = Not determined. NA = Not applicable.



Investigations



Initial Scheme



14.06.2023	P01	FOR INFORMATION	DP	
Date	Rev	Description	Drawn	Chkd

Civic Engineers



Project
Echo Street, Manchester

Title
Foundation Level - Concrete Core Location Suggestions

Project Number	Drawing Number	Scale @ A3	Revision
1596-01	SK_008	N.T.S	P01



Structural Design



FACADE DL = 5 kN/m

NOTE:
THIS DRAWING HAS BEEN ISSUED FOR CONSTRUCTION FOR THE
PURPOSE OF COLUMN SETTING OUT ONLY. ALL BWIC OPENINGS,
UPSTANDS SETTING OUT IN ABEYANCE.

TYPICAL FLOOR		DL = 0.9 KPa LL = 1.5 KPa	RESIDENT/AMENITY		DL = 0.5 KPa LL = 4 KPa	ROOF LOADING (GREEN + BLUE)		DL = 1.1 KPa LL = 2.25 KPa	ROOF LOADING (STONE BAL)		DL = 1.15 KPa LL = 0.75 KPa
HALLWAY		DL = 0.5 KPa LL = 3 KPa	EXTERNAL (GROUND)		DL = 3.15 KPa LL = 5 KPa	ROOF LOADING (TYPICAL)		DL = 0.6 KPa LL = 0.75 KPa			
STAIRS		DL = 0.5 KPa LL = 4 KPa	PLANT ROOM 1		DL = 0.6 KPa LL = 5 KPa	ROOF LOADING (MID LEVEL)		DL = 2.8 KPa LL = 2.25 KPa	CONSTRUCTION		DL = 1.5 KPa LL = 0.75 KPa
OFFICE LOADING		DL = 0.5 KPa LL = 2.5 KPa	PLANT ROOM 2		DL = 0.6 KPa LL = 7.5 KPa						

PROJECT: IQ STUDENTS, ECHO STREET

TITLE: L12 LOADING PLAN

DATE CREATED: JAN 05

SCALE: 1:100

STATUS: FOR INFORMATION

PROJECT No: 2925

SCALE: 1:100

DATE CREATED: JAN 05

DRAWN: NDM

CHECKED: DP

DRAWING No: 63073-CCE-ZZ-DR-S-23061

REV: P01

CIVIC ENGINEERS


www.civicingineers.com

Please note that piles with the same pile diameter, pile depth, rock socket, main reinforcement, links, required anchorage and rebar length have been grouped together. The maximum ULS vertical, SLS vertical and SLS lateral capacities have been taken for all the piles. Pile testing for x,y,z has been recorded to satisfy that the piles installed are to specification or an enhancement of the specification.


Values from TSD model: 23-11-02 Foundation master model V64				LEADING Pile Design	Pile Reference	Location	No of Piles	ULS			ULS			SLS			SLS
Comment	ULS Vertical with ILR	SLS Vertical with ILR	SLS Lateral with ILR					COMBINATION 1			COMBINATION 2			REPRESENTATIVE ACTIONS			SLS Horizontal Action
								Vertical Action Max	Vertical Action Min	Horizontal Action	Vertical Action Max	Vertical Action Min	Horizontal Action	Vertical Action Max	Vertical Action Min	Horizontal Action	
Conditional Formatted																	
	3075	2250	30.0	CPA001 ULS 3500kN SLS 2500kN SLS Lat 90kN	CPA001	West	1	3500	100	100	2700	100	90	2500	100	90	
	2850	2100	30.0		CPA002	West	1	3500	100	100	2700	100	90	2500	100	90	
	2625	1950	30.0		CPA003	West	1	3500	100	100	2700	100	90	2500	100	90	
	2450	1825	30.0		CPA004	West	1	3500	100	100	2700	100	90	2500	100	90	
	2300	1700	30.0		CPA005	West	1	3500	100	100	2700	100	90	2500	100	90	
	2050	1525	30.0		CPA006	West	1	3500	100	100	2700	100	90	2500	100	90	
	1750	1300	30.0		CPA007	West	1	3500	100	100	2700	100	90	2500	100	90	
	3350	2475	30.0		CPA008	West	1	3500	100	100	2700	100	90	2500	100	90	
	3025	2250	30.0		CPA009	West	1	3500	100	100	2700	100	90	2500	100	90	
	2800	2050	30.0		CPA010	West	1	3500	100	100	2700	100	90	2500	100	90	
	2625	1950	30.0		CPA011	West	1	3500	100	100	2700	100	90	2500	100	90	
	2475	1825	30.0		CPA012	West	1	3500	100	100	2700	100	90	2500	100	90	
	2225	1625	30.0		CPA013	West	1	3500	100	100	2700	100	90	2500	100	90	
	1975	1425	30.0		CPA014	West	1	3500	100	100	2700	100	90	2500	100	90	
	3425	2500	30.0		CPA015	West	1	3500	100	100	2700	100	90	2500	100	90	
	3100	2300	30.0		CPA016	West	1	3500	100	100	2700	100	90	2500	100	90	
	2800	2075	30.0		CPA017	West	1	3500	100	100	2700	100	90	2500	100	90	
	2625	1900	30.0		CPA018	West	1	3500	100	100	2700	100	90	2500	100	90	
	2500	1850	30.0		CPA019	West	1	3500	100	100	2700	100	90	2500	100	90	
	2275	1675	30.0		CPA020	West	1	3500	100	100	2700	100	90	2500	100	90	
	2000	1475	30.0		CPA021	West	1	3500	100	100	2700	100	90	2500	100	90	
	3475	2500	30.0		CPA022	West	1	3500	100	100	2700	100	90	2500	100	90	
	3125	2300	30.0		CPA023	West	1	3500	100	100	2700	100	90	2500	100	90	
	2875	2100	30.0		CPA024	West	1	3500	100	100	2700	100	90	2500	100	90	
	2700	1950	30.0		CPA025	West	1	3500	100	100	2700	100	90	2500	100	90	
	2525	1850	30.0		CPA026	West	1	3500	100	100	2700	100	90	2500	100	90	
	2225	1625	30.0		CPA027	West	1	3500	100	100	2700	100	90	2500	100	90	
	1925	1400	30.0		CPA028	West	1	3500	100	100	2700	100	90	2500	100	90	
	3250	2350	30.0		CPA029	West	1	3500	100	100	2700	100	90	2500	100	90	
Pile integrity test failure - pile removed from model	0	0	0.0		CPA030	West	1	3500	100	100	2700	100	90	2500	100	90	
	2800	2000	30.0		CPA031	West	1	3500	100	100	2700	100	90	2500	100	90	
	2600	1900	30.0		CPA032	West	1	3500	100	100	2700	100	90	2500	100	90	
	2400	1775	30.0		CPA033	West	1	3500	100	100	2700	100	90	2500	100	90	
	2075	1500	30.0		CPA034	West	1	3500	100	100	2700	100	90	2500	100	90	
	1700	1225	30.0		CPA035	West	1	3500	100	100	2700	100	90	2500	100	90	
	3525	2575	0.8	CPA036	CPA036	West	1	5000	2300	0	3800	2300	0	3500	2300	0	
	2450	1775	0.8	ULS 5000kN SLS 3500kN SLS Lat 0kN	CPA037	West	1	1900	800	0	1400	800	0	1300	800	0	
	2325	1675	0.8	CPA038	West	1	1900	800	0	1400	800	0	1300	800	0		
	2100	1500	0.8	CPB144	CPA039	West	1	2700	1100	0	2100	1100	0	1900	1100	0	




Pile Layout



Foundation Layout







EXTENT OF CONCRETE COVER TO FACE OF EXISTING CORE BASE TO BE SCABBLED BACK TO EXPOSE REINFORCEMENT. REINFORCEMENT TO BE SURVEYED TO DEVELOP DRILL AND FIX DETAIL OF NEW STRUCTURE TO EXISTING BASE.

9 B20 13 DOWELS
Dowel bars needed here also.
All edge distances to be minimum 300mm. Spacing between dowels not to be less than 300mm

All edge distances to be minimum 300mm. Spacing between dowels not to be less than 300mm

NOTE:
SETTING OUT OF DOWELS TO BE DETERMINED UPON REMOVAL OF CONCRETE COVER TO AVOID EXISTING REINFORCEMENT

ALL DOWEL BARS TO BE INSTALLED USING HILTI HIT RE 500 V4 INJECTION RESIN WITH REBAR



STANDARD NOTES
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S AND ENGINEER'S DRAWINGS AND THE SPECIFICATIONS.
2. THIS DRAWING SHOULD NOT BE SCALED.
3. ALL DIMENSIONS ARE TO BE VERIFIED BY THE CONTRACTOR ON SITE.
4. ALL DISCREPANCIES SHOULD BE REPORTED TO C.E. PRIOR TO THE COMMENCEMENT OF WORKS.

© CIVIC ENGINEERS LIMITED
KEY

NOTES
1. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, M-E AND CIVIL ENGINEERS DRAWINGS.
2. ALL CONCRETE GRADE C40/50 U.N.O.
3. COVER TO REINFORCEMENT TO BE U.N.O.:
SIDE 50mm
TOP 50mm
BOTTOM 75mm
4. REBAR CALL OFF:
15 H12 201-150 B1
BAR LAYER
BAR SPACING
BAR MARK
BAR TYPE AND DIA
NUMBER OF BARS

5. MINIMUM LAPS FOR GRADE 500 REINFORCEMENT TO BE U.N.O.:

GOOD BOND		POOR BOND	
HB	HSD	HB	HSD
H8	290	H8	420
H10	350	H10	500
H12	450	H12	640
H16	650	H16	930
H20	860	H20	1220
H25	1110	H25	1590
H32	1420	H32	2030

6. MINIMUM ANCHORAGE FOR GRADE 500 REINFORCEMENT TO BE U.N.O.:

GOOD BOND		POOR BOND	
HB	HSD	HB	HSD
H8	270	H8	390
H10	350	H10	490
H12	430	H12	590
H16	550	H16	790
H20	690	H20	980
H25	860	H25	1240
H32	1100	H32	1570

7. LAPS SHOULD BE APPROPRIATE TO THE SMALLER BAR BEING LAPPED AND THE GOOD/POOR BOND CONDITION:
FOR 250 < h < 600
FOR h > 600

8. ALL REINFORCEMENT BARS SHALL BE IN ACCORDANCE WITH BS4482:2020 WITH YIELD STRENGTH OF 500MPa
9. ABBREVIATIONS:
T TOP
B BOTTOM
NF NEAR FACE
FF FAR FACE
SF SIDE FACE
AB ALTERNATE BARS
ABS ALTERNATE BARS STAGGERED
ABR ALTERNATE BARS REVERSED
U U BAR
L L BAR
LK LINKS
10. BARS DETAILED ON THIS DRAWING ARE LISTED ON THE BAR SCHEDULE: ECHO-CCE-ZZ-FN-SH-S-5011

Date	Rev	Description	CE	YH
15.09.23	001	ISSUED FOR CONSTRUCTION		

Civic Engineers
Civic's Warehouse, 77 Dale St, Manchester, M1 2HS, Tel: 0161 228 6757
London: 33 Mill Street, London SE1 2AK, Tel: 020 7253 2977
Tower Works, Unit 02-03, Globe Rd, Leeds, LS11 5QG, Tel: 0113 2025 130
Glasgow: 45 West Nile St, Glasgow, G1 2PL, Tel: 0141 370 1829
www.civicingineers.com


Project
**ECHO STREET
MANCHESTER**

Title
**BLOCK C
BASE REINFORCEMENT
SHEET 1**

Status
CONSTRUCTION


**ECHO-CCE-ZZ-FN-SK-S-5011D
DP for Civic Engineers
19.10.23**






CORE BASE C - FOUNDATION

SCALE: 1:50




CORE C - DOWEL BAR INSTALLATION DETAIL A

SCALE: 1:25




CORE C - DOWEL BAR INSTALLATION DETAIL B

SCALE: 1:25




CORE C - DOWEL BAR INSTALLATION DETAIL C

SCALE: 1:25



CORE C - DOWEL BAR INSTALLATION DETAIL D


SCALE: 1:25



CORE C - DOWEL BAR INSTALLATION DETAIL E

SCALE: 1:25

Superstructure



STANDARD NOTES

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S AND ENGINEER'S DRAWINGS AND THE SPECIFICATIONS.
- THIS DRAWING SHOULD NOT BE SCALED.
- ALL DIMENSIONS ARE TO BE VERIFIED BY THE CONTRACTOR ON SITE.
- ALL DISCREPANCIES SHOULD BE REPORTED TO C.A./E.A. PRIOR TO THE COMMENCEMENT OF WORKS.

REF.	SECTION SIZE (mm)
RCC1	1200 x 350 RC COLUMN
RCC2	1400 x 450 RC COLUMN
RCC3	650 x 350 RC COLUMN
RCC4	800 x 400 RC COLUMN
RCC5	750 x 250 RC COLUMN
RCC6	450 x 350 RC COLUMN
RCC7	650 x 450 RC COLUMN
RCC8	950 x 300 RC COLUMN
RCC9	950 x 250 RC COLUMN

REF.	SECTION SIZE (mm)
RCC10	500 x 300 RC COLUMN
RCC11	1400 x 350 RC COLUMN
RCC12	550 x 350 RC COLUMN
RCC13	950 x 350 RC COLUMN
RCC14	750 x 350 RC COLUMN
RCC15	750 x 300 RC COLUMN
RCC16	1200 x 250 RC COLUMN
RCC17	500 x 350 RC COLUMN
RCC18	600 DIA. RC COL.

REF.	SECTION SIZE (mm)
RCC19	650 DIA. RC COL.
RCC20	800 x 300 RC COLUMN
RCC21	650 x 300 RC COLUMN
RCC22	550 x 300 RC COLUMN
RCC23	350 x 350 RC COLUMN
RCC24	750 x 400 RC COLUMN

REFERENCE	SIZE (mm)
W1	225 THK RC WALL
W2	250 THK RC WALL
W3	300 THK RC WALL
W4	350 THK RC WALL

THIS DRAWING REPRESENTS THE LAST VERSION ISSUED FOR CONSTRUCTION. THE DRAWING HAS NOT BEEN VERIFIED BY SITE SURVEY AND ALLOWABLE CONSTRUCTION TOLERANCES MAY HAVE RESULTED IN DIFFERENCES BETWEEN THIS DRAWING AND THE FINISHED BUILDING

LEGEND

- DENOTES EXTENT OF CAST-IN CONTINUITY STRIP (ANCON EAZISTRIP - OR SIMILAR APPROVED) CENTRED ON MID DEPTH OF RC STRUCTURAL SLAB.
- ⊕ DENOTES LOCATION OF BUILDERS WORKS HOLE / SERVICES (SHOWN INDICATIVELY) - REFER TO ARCHITECT'S DRAWINGS FOR SETTING OUT AND LOCATIONS. NOTE: BUILDERS WORKS HOLES LESS THAN 200mm GENERALLY NOT SET OUT IN DRAWINGS, WHERE BWIC SHOWN REINFORCEMENT TO BE LOCALLY DISPLACED TO ALLOW SERVICES TO PASS THROUGH SLAB.
- ⊗ DENOTES LOCATION OF SERVICE RISERS ASSUMED TO BE CAST IN 'SOFT SPOTS' IN SLAB WITH CAST-IN CORED PENETRATIONS. SOFT SPOTS DO NOT CONSTITUTE VOIDS IN SLAB. REINFORCEMENT TO BE PRESENT WITHIN ZONES AND SETTING OUT OF BWIC IN THESE AREAS TO BE ACCORDANCE WITH GUIDANCE SHOWN ON LOCAL DISPLACEMENT DETAIL ON DRAWING 63073-CCE-ZZ-DR-S-21110

NO.	DATE	BY	DESCRIPTION	STATUS
14.01.26		CB	AS DESIGNED ISSUE	AS
22.05.24		CB	REVISIONS TO CORES B & C	PM
05.06.24		CB	CORE C SLAB SETTING OUT, UPDATED AND REINFORCEMENT BARS ADDED	IS
06.02.24		CB	SOFT SPOT SETTING OUT ADDED	PM
23.05.24		CB	CONSTRUCTION DETAILS	PM
08.12.23		CB	ISSUED FOR CONSTRUCTION	PM
07.08.23		CB	STAGE 3 ISSUE	PM
24.07.23		CB	PRELIMINARY WP ISSUE	PM
		REV	DESCRIPTION	CHD

PROJECT
IQ STUDENTS, ECHO STREET

Civic Engineers

14-01-26 LONDON
0203 250 5300
www.civicingineers.com

DRAWING STATUS
AS DESIGNED






DRAWING NO: 63073-CCE-ZZ-05-DR-S-23005
REV: C06



Superstructure





Superstructure




— Substructure#3 - Tower C - Max
— Substructure#3 - Tower C - Mean

Superstructure









CIVIC





CIVIC



CIVIC



CIVIC



CIVIC



Key Points

- Forensic review of what was already in ground both desk based and insitu to give confidence there were opportunities for reuse.
- Creating a structural grid compatible with the existing foundations while accommodating additional height without exceeding installed pile capacities.
- Use of repetitive grids to eliminate transfer structures and preserve internal layouts.
- Super thin slabs introduced to free up capacity within piles to accommodate additional storeys.
- Structural wind to reduce wind loads and core wall thickness, tracked down to piles.
- Detailed analyses of construction loads and early strength profiles to improve construction programme
- Assessment of slab behaviour under temporarily high loads and alternating load sequences before full concrete strength developed.



Key Achievements

- Reuse of over 400 piles with only 7 new permanent piles added.
- Elimination of over 350m³ of concrete and 300 tonnes of embodied carbon.
- Demonstration of how structural design can significantly reduce environmental impact without compromising performance



Key Takeaways

- Innovative and considerate engineering is fundamentally important in all buildings, especially tall buildings.
- Collaboration and engineers' relationship with the Project Team.
- Lock in opportunities
- Building Safety Regulator and pragmatic sensible design
- Compromise without sacrifice

CIVIC

Thank You

dan.podesta@team-civic.com

team-civic.com

**thriving
together**